
Address: 14 Nile Street



**Legal Description:** Lot 179, Part of Lot 555, Plan 20

**Designation By-law: 171-85** 

**By-Law Designation Date:** December 16, 1985

**Date of Construction: 1878** 

Architectural Style: Italianate

Architectural Description: two storey irregular plan; yellow brick; hip roof with a flat centre section and gables roofs; first floor on the left; three sided bay window with segmentally arched windows in each section; the centre window is two panes over two whereas the windows on the sides are one pane over one pane; each window I the house has a raised brick voussoir; the frieze board under the upstairs bay window has decorative brackets; the rectangular front porch with the flat roof is supported by decorative brackets and by a grouping of three reeded Doric columns in each front corner and a single column on each side at the rear of the porch; the door under the porch is a double door with a segmentally arched top; there are raised bricks at the corners of the house and a brick pilaster on the left side of the porch; second floor; the bay window is the same as on the first floor except it has a small wrought iron railing at the top of the flat roof; there is a rectangular window above this under the gable; on the right side is a segmentally arched one pane over one pane window. A modern infill has been constructed between the right hand front wall and the side wall with the projecting gable, which has a bay window on the first floor; the left side of the house has an enclosed porch on the first floor and two segmentally arched windows on the second floor; the tail of the house also has brackets under the eaves and segmentally arched windows.

The house as built by Peter Robinson Jarvis.